

PARAMBU — SOAP & OIL UNIT



CONSTRUCTION NOTES

- Room separators are 2" (50 mm) panels — cement board / PUF / gypsum on a light frame. No masonry wall between rooms.
- East-west closes exactly: 16'-0" west rooms + 4'-0" path + 16'-0" east rooms = 36'-0". Every room is 16'-0" deep.
- W2, W3 and W4 are one soap making and curing room. W5 is the QC room. W6 remains the office.
- E4 and E5 are one oil making and filling room. E3 is powder and facepack. E2 is finished product.
- W1 and E1 are one raw-material room across the north; the 4' path stops there. From D1: 3' men door and raw-material door into E1, 6' door into E2, and a door onto the central path.
- Floor: IPS / epoxy with 4" coved skirting, graded to trapped gullies. Ceiling 12'-0" clear over soap and oil rooms.
- Windows 4'-0" x 3'-0" on the west and east walls with insect screens; exhaust fan over the lye mixing bench and over the cold press.
- Toilet block detached, minimum 25'-0" clear of the north wall, never opening into a production room. Hand wash at the D1 entry path.