

PARAMBU — SOAP & OIL UNIT



CONSTRUCTION NOTES

- Room separators are 2" (50 mm) panels — cement board / PUF / gypsum on a light frame. No masonry wall between rooms.
- East-west closes exactly: 16'-0" west rooms + 4'-0" path + 16'-0" east rooms = 36'-0". Every room is 16'-0" deep.
- West bay north-south: 10 + 10 + 10 + 19'-2" + 10 + 10 = 69'-2". The remaining 10" is six 2" panels = 70'-0".
- East bay north-south: five 10'-0" rooms + two 9'-6" loading paths = 70'-0". Both 7'-0" east doors sit in those paths.
- Internal doors 3'-6" x 7'-0", all opening into the room, not into the 4'-0" path. External doors D1 and D2 are 7'-0" rolling shutters facing east.
- Floor: IPS / epoxy with 4" coved skirting, graded to trapped gullies. Ceiling 12'-0" clear over soap and oil rooms.
- Windows 4'-0" x 3'-0" on the west and east walls with insect screens; exhaust fan over the lye mixing bench and over the cold press.
- Toilet block detached, minimum 25'-0" clear of the north wall, never opening into a production room. Hand wash at the D1 entry path.